

Project List

Title	Description	Location	Est. Schedule		Useful Life	
			Start	Completion	Min	Max
Bonita Canyon and Ford Road Pavement Rehabilitation (20/21)	This project is located on Bonita Canyon Drive and Ford Road and involves cold milling and overlaying the existing asphalt concrete pavement with rubberized asphalt concrete. Deteriorated concrete improvements will also be reconstructed. Impacted utilities will be adjusted to grade. The new pavement will also be restriped. Final design is scheduled to be completed by April 2020 and construction will be completed by winter 2020. The estimated useful life of this project is 15 years minimum.	This project is located on Bonita Canyon Drive and Ford Road from Jamboree Road to State Route 73.	3/12/2019	12/1/2020	15	20
Cameo Highlands Street Pavement Reconstruction (19/20 Carryover)	The project involves removing the deteriorated asphalt concrete pavement, reconstructing new asphalt concrete pavement, and reconstructing isolated failed concrete improvements such as curbs, sidewalks, driveway approaches, and access ramps. Impacted utilities will be adjusted to grade. The new pavement will also be restriped. Final design is scheduled to be completed by Spring 2020 and construction will be completed by Winter 2020. The estimated useful life of this project is 15 years minimum.	This project is located in the residential neighborhood of Cameo Highlands off Cameo Highlands Drive and East Coast Highway.	9/1/2019	12/1/2020	15	20
Bison Avenue, San Joaquin Hills Road and San Nicolas Drive Pavement Rehabilitation (18/19 Carryover)	This project involves cold milling and overlaying the existing asphalt concrete pavement with rubberized asphalt concrete. Deteriorated concrete improvements will also be reconstructed. Impacted utilities will be adjusted to grade. The new pavement will also be restriped. Final design was completed in November 2019. Construction will be completed by Spring 2020. The estimated useful life of this project is 15 years minimum.	This project is located on Bison Avenue from Jamboree Road to State Route 73, San Joaquin Hills Road from Jamboree Road to MacArthur Boulevard, and San Nicolas Drive from Newport Center Drive to Avocado Avenue.	10/23/2018	5/1/2020	15	20
MacArthur Blvd and University Dr Pavement Rehabilitation (17/18 Carryover)	This project involves cold milling and overlaying the existing asphalt concrete pavement with rubberized asphalt concrete. Deteriorated concrete improvements will also be reconstructed. Impacted utilities will be adjusted to grade. The new pavement will also be restriped. Final design was completed in March 2019. Construction was completed in September 2019. The estimated useful life of this project is 15 years minimum.	MacArthur Boulevard from Ford Road/Bonita Canyon Drive to State Route 73 and University Drive from Jamboree Road to State Route 73.	11/28/2017	9/26/2019	15	20